





#### Housekeeping

- Hybrid meeting
- Presentation followed by Q&A
- Virtual attendees type questions in the chat
- Project team will read questions aloud and then provide a response



#### Agenda

- Project overview
- Environmental decision update
- Innovation process update
- Recommended innovations
- Environmental commitments
- Next steps
- Project Advisory Committee discussion
- Public comment opportunity








#### **Purpose and Need**

- Improve traffic flow and level of service
- Improve safety
- Correct geometric deficiencies
- Maintain connections to key regional and national transportation corridors




#### **Project Description**


- 8-mile corridor from Dixie Highway (KY) to the Western Hills Viaduct (OH)
  - 5 miles of I-71/I-75 in KY
  - 3 miles of I-75 in OH
- Widen I-71/I-75
- Rebuild all overpass bridges and interchange
- Build a collector-distributor system between Covington and Cincinnati



#### **Project Description**

- Update the existing Brent Spence Bridge
  - Rehabilitate the structure
  - 3 lanes on each deck
  - Inside/outside shoulders
  - Carry local traffic
- Build new companion bridge
  - West of existing Brent Spence Bridge
  - 5 lanes on each deck
  - Carry interstate traffic






#### **Project Cost**

\$3.6 Billion


(includes planning, design, property acquisition, construction, construction, construction management services, agency labor)






#### **Environmental Decision Update**

- 5 public hearings held in February 2024
  - 209 public comments (165 commenters)
  - 6 federal, state and local agency comments
- Responses prepared for all comments
- Minor updates to the supplemental environmental assessment
- FHWA issued a Finding of No Significant Impact (FONSI) on May 8, 2024
- All documents on project website (<u>www.brentspencebridgecorridor.com/documents</u>)









- Progressive design-build contract (Phase III)
- Supplemental environmental assessment evaluated the base design
- Innovation concepts
  - Improve project quality
  - Reduce costs
  - Shorten schedule
  - Support project goals
  - Support at the local level



#### **Contract Objectives**

- Maximize the project scope within the programmed funding amounts through innovation, design optimization and effective risk mitigation
- Achieve effective project delivery
- Open the new companion bridge to traffic in 2029
- Minimize traffic disruption during construction, with minimal detours or diversion of traffic to local streets
- Minimize physical intrusion and impact
- Maximize public investment by minimizing the footprint
- Minimize the footprint to maximize potential developable space

- Improve neighborhood connectivity across the interstate
- Build the project with a context sensitive design that fits within the community
- Provide strong aesthetic value
- Improve the local road aesthetics when crossing the interstate
- Provide opportunities for workforce development and DBE utilization
- Create best environmental outcomes
- Design for sustained quality of life





#### **Timeline**

Design-build team notice to proceed......October 2023 Draft analysis of innovations ...... February 2024 Continue to vet innovations ................................. March 2024 - present

- 117 refinements evaluated by KYTC and ODOT
- Vetted with local municipalities
- By the numbers
  - 26 recommended
  - 24 dismissed
  - 67 still under review








#### Kentucky

- Vertical profile optimization
- Pike Street access optimization
- Hillside cut alignment shift

#### Ohio

- Southbound roadway reconfiguration
- Combination of 2nd and 3rd Street connections
- US-50 Roadway Consolidation
- Realization of Street Grid Concept





- Reconfigure southbound collector-distributor road
- Adjust West 5th Street
- Create gateway at Crescent Avenue/West 3rd Street
- Lower mainline roadway by about 30 feet














- West 5th Street closed under I-71/I-75
- Traffic rerouted via
   Philadelphia and West 3rd
   Streets





- Improved viewshed east and west of interstate
- Enhanced West 3rd Street connectivity for all modes of travel
- Provide gateway opportunity and improved integration of West 5th Street traffic into Covington
- Reduced construction and long-term maintenance costs







#### 2 | Pike Street Access Optimization

- Eliminates direct interstate access at West 9th Street
- Maintains existing interstate access at Pike Street
- Maintains frontage road concept







#### 2 | Pike Street Access Optimization

- Maintains residential character of West 9th Street
- Eliminates traffic signals on West 9th Street
- Minimizes physical and visual impacts to the Goebel Park Complex








#### 3 | Hillside Cut Alignment Shift

- Shifts I-71/I-75 east
- Avoids significant rock cut and retaining wall construction
  - No rock cut or tiered wall west of I-71/I-75
  - 94,000 square foot reduction in retaining walls





#### 3 | Hillside Cut Alignment Shift


- Substantially reduces costs
- Saves construction time






# Cincinnati Findlay St W Liberty St W Sth St Exzard Charles Dr W 4th St W 50 W 50 W 4th St W 5th St Covington W 12th St W 12th St W 22th St W 12th St

#### **Ohio Recommended Innovations**



# Cincinnati Findley St WLiberty St WLiberty St Ezzard Charles Dr W 4th St W 5th St Covington Ou Golf Vent Center W 12th St W 12th

#### **Ohio Recommended Innovations**





## 1 | Southbound Roadway Reconfiguration


- Southbound I-71/I-75 moved to outside
- Southbound collectordistributor roadway moved to inside
- Southbound I-75 constructed offline
- Simplified bridge designs
- Simplified maintenance of traffic





## 1 | Southbound Roadway Reconfiguration


- Improves constructability
- Reduces costs
- Improves safety





## 1 | Southbound Roadway Reconfiguration


- Western Avenue ramp to southbound I-75 removed
- Alternate routes
  - Proposed 9th Street entrance (+0.6 mile)
  - Existing Freeman Avenue interchange (+1.25 mile)
- Low volumes
  - 300 vehicles in PM peak hour





#### 2 | Combination of 2nd and 3rd Street Connections


- Southbound I-75 ramps to 2nd and 3rd Streets
- Traffic rerouted through upgraded at-grade 2nd and 3rd Street intersections
- Reduced vertical design challenges





#### 2 | Combination of 2nd and 3rd Street Connections

- Reduces costs
- Enhances street grid system
- Improves safety at the 2nd Street and Elm Street intersection
- Reduces impacts to city parking lots





#### 3 | US-50 Roadway Consolidation

 Reconfigure US-50 eastbound and westbound to follow a single alignment







#### 3 | US-50 Roadway Consolidation

- Reduces footprint
- Improves geometrics
- Allows for future extension of
   5th Street to Gest Street








#### 3 US-50 Roadway Consolidation


- Ramp from westbound US-50 to Gest Street removed
- Traffic rerouted to existing
   Linn Street exit
- Relatively low volumes
  - 580 vehicles in the AM peak hour





#### 3 US-50 Roadway Consolidation

- Ramp from eastbound US-50 to 2nd Street removed
- Alternate routes
  - Existing Freeman Avenue exit (+1 mile)
  - 5th Street exit (+1/2 mile)
- Low volumes
  - o 220 vehicles in AM peak hour
  - o 90 vehicles in PM peak hour





#### 4 | Realization of Street Grid Concept

- New intersection at Gest and 9th Streets
- Improved intersection at Gest and 7th Streets
- New intersection at Gest and 6th Streets
- 5th Street extended to
   Queensgate with potential
   future extension to Gest Street







#### 4 | Realization of Street Grid Concept

- Improves connections to Queensgate for all modes of travel
- Shortens pedestrian crossing from downtown to Queensgate
- Condenses interchange footprint
- May open up additional developable land








#### 4 | Realization of Street Grid Concept







#### 4 | Realization of Street Grid Concept


- Improves east-west connectivity between downtown and Queensgate
- Connects across 3rd, 5th, 6th
   7th, and 9th Streets








#### 4 | Realization of Street Grid Concept



# Cincinnati Findlay St WLiberty St WLiberty St Ezzard Charles Dr Rog 92 Walnut 92 W 4th St W 5th St Covington au Golff center W 12th St Rog 92 W 4th St W 5th St Covington au Golff cent Center W 12th St Rog 92 W 4th St W 5th St Covington

#### **Ohio Recommended Innovations**








- Commitments to be carried out by KYTC and ODOT as the project progresses through detailed design and construction
- 62 total environmental commitments
  - Commitment 1: Innovation process
  - Commitment 51: Specific design refinements to be evaluated
  - Commitment 53: Ongoing PAC coordination


#### **Environmental Commitment 51**

The following refinements suggested during public involvement activities will be further evaluated during the innovation process for the Phase III progressive design-build contract:

- a. Eliminate the 3rd Street ramp to the northbound collector-distributor system in Cincinnati and redirect traffic to the proposed connection at the end of the Clay Wade Bailey Bridge;
- b. Reconfigure the lanes on the Clay Wade Bailey Bridge to add bicycle lanes;
- c. Reconfigure 6th Street in Cincinnati to accommodate two-way traffic; and
- d. Design concepts submitted by the Bridge Forward Coalition.



 Recommended Ohio innovations and Bridge Forward design accomplish many of the same goals



IN **OBJECTIVES** IN Less overhead BF IN BF work. Improved safety for Queensgate CBD to Larger work area. connections via Less temporary motoring Queensgate IN 6th, 7th, and connection IN BF pavement. public. IN Contractor Reduced traffic 9th. Allows for approximately IN Similar to base future extension **575ft/460ft** 11 acres/ impacts during preferred for Comparable to base design. along 5th. construction. worker safety. of 5th. 1% decrease design. 14 acres Developable Reconnecting **Pedestrian** Constructability **Operation** Safety **Schedule** Cost Communities Access Land **Cannot function** Additional 1-2 Constrained Increased 25-30% as submitted. work area. worker and increase years. motoring public Operations fail Trench work **DOES NOT MEET** BF BF area. Multi-level even with exposure to **OBJECTIVES** high-risk traffic significant construction. design changes. conditions. BF BF BF Recommended Ohio IN *Innovations* 

**MEETS OR EXCEEDS** 

Bridge Forward Concept



#### **Next Steps**



#### **Next Steps**

- Conduct outreach to community councils, neighborhood groups, and other stakeholders
- Update and confirm traffic and environmental studies for the recommended innovations
- Proceed to detailed design (Phase III)
  - 30% plans by August 2024
  - Contractual estimate update
  - Identify early work packages







#### **Public Comments**

- Please state your name.
- Type a comment in the chat (virtual attendees).





### THANK YOU!

www.brentspencebridgecorridor.com



